



Test Report: Reconstituted Wood Products Testing

Timber Testing Centre Reference S-29282-2022
Report Number 20220307-154525
Testing Status Contract
Samples Submitted 21/02/2022
Date of Issue 07/03/2022

Stuart Toakley
Sales and Marketing Manager
Borg Manufacturing Pty Ltd trading as Australian Panel Products
2 Wella Way, Somersby, NSW, 2250, Australia

TESTING DETAILS

Test Method(s):

As per method indicated in the Test Results table.
Samples are cut in accordance with AS/NZS 4266.1.

Test Location:

Timber Testing Centre, Unit 2, 107 Northlink Place, Virginia, QLD, 4014

Quote Number: TTC202206

LIMITATIONS OF REPORT

All results reported apply only to the sample tested and apply to the sample as received by the Timber Testing Centre. This report shall not be reproduced except in full. Results do not extend to any other manufactured product or to ongoing manufactured products. The Timber Testing Centre makes no claims to the ongoing ability of the manufacturer to meet required manufacturing standards. The results of this report do not determine the compliance of the test material to any manufacturing standards. Prior treatment, handling, conditioning and exposure and its effect on the sample prior to testing have not been verified. This report shall not be reproduced or published by the customer without the written consent of the Timber Testing Centre.

TEST RESULTS

Number of samples submitted for testing: 1

Testing Period: 21/02/2022 through 07/03/2022

Sample Description * Standard N/A Grade Source Sample Number Thickness (mm) 0	Dimension Comment Product Description 2-185: Structapanel 2-186: Plywood - raw board 2-187: Rflor 2-188: Yellow tongue (glossy) 2-189: Yellow tongue (matt)
--	--

Batch	Test	Method	Result (Mean)	Std Dev	Units
2-185	Surface Water Absorption	AS/NZS 4266.1 S13	34.10	0.00	g/m2
2-186	Surface Water Absorption	AS/NZS 4266.1 S13	1108.70	0.00	g/m2
2-187	Surface Water Absorption	AS/NZS 4266.1 S13	6.60	0.00	g/m2
2-188	Surface Water Absorption	AS/NZS 4266.1 S13	43.60	0.00	g/m2
2-189	Surface Water Absorption	AS/NZS 4266.1 S13	66.20	0.00	g/m2

(R) against the Batch indicates a Re-Test has been conducted.

* Sample description information has been provided by the client

Additions/Deviations/Exclusions:

A cutting plan is not provided. The mean and standard deviation values reported apply to the results of replicate test pieces. Panels tested for certification purposes have only had one formaldehyde test performed. The duplicate pieces shall only be tested in the case of abnormal or failed results. Moisture content testing is performed without the use of a drying desiccator. The internal desiccator temperature check for formaldehyde testing has not been recorded. Wet Bending Strength – Method C has been tested at a boiling temperature of 100oc.

SAMPLING DETAILS

The Timber Testing Centre did not conduct sampling. Samples were submitted to the Timber Testing Centre by the client.

Regards,



Suzie Steiger

General Manager